

# Runway Rehab North (RRN)

- **Construction Year: 2026**
- **Construction Seasons: Single**
- **Access For Construction: Two Displaced Thresholds (6000 & 7000)**
- **Major work highlights**
  - Pavement Rehab (8 inch to correct blistering) ~2,200 LF
  - Grading to Improve Drainage ~60,000 CY
  - Adding Compost Amended Vegetated Filter Strips for runoff treatment
  - Underdrain System Enhancements
  - Replacement of in-pavement RWY Light Cans ~200 Cans
  - Removal of TW A2
  - Hot Spot Mitigation - Add Alt #1
  - LED Rwy Edge Lights full length – Add Alt #2
- **FAA Standards Corrected:**
  - RSA Grading
  - Drainage system located outside RSA
  - Removal of non-standard taxiway
  - Hot Spot Mitigation and aligned taxiway removal

