



Moisture Remediation for New Start Center of Everett 1602 SE Everett Mall Way Everett, WA 98201 Contract # SW-24-017LY Dated: 9 October 2024 CO Number: 02

Date: 27 November 2024

Contractor:

Accurate Assessment Environmental 1331 Meador Ave., Suite J-105 Bellingham, WA 98229

The Contract is changed as follows:

### Pursuant to part 17 of the General Conditions the contractor shall:

After the initial scope of work began, additional mold impacted GWB has been identified, and ACM was discovered behind the GWB adhered to the backside of GWB in a large number of units. Change order quantities and locations of both additional mold-impacted GWB and ACM were defined by Atlas.

The scope of work relative to the asbestos bearing materials is required to comply with Class 2 abatement work, including but not limited to Asbestos Abatement Supervisor daily rate, daily air monitoring, proper dust mitigating work procedures, ACM waste transportation and disposal, air monitoring record keeping, and air monitoring laboratory analysis. See WAC 296-62-07712 Requirements for Asbestos Activities in Construction and Shipyard Work.

Pricing for non-asbestos bearing gypsum board is based on the unit pricing provided in the RFP (\$193 per 10 SF). Unit pricing for the asbestos bearing gypsum board is \$171.50 per 10 SF, which is less than the non-asbestos bearing gypsum board.

Material	Contract Sum Change	Contract Schedule		
		Change		
2530 SF Gypsum Wall Board	\$48,829.00	10 days		
2600 SF of Asbestos Bearing Gypsum Wall Board	\$44,590.00	10 days		
Total	\$93,419.00	20 days		

New Contract Sum	\$319,188.00
Change to Contract Sum by this Change Order	\$93,419.00
Change to Contract Sum by Previous Change Orders to date	\$37,540.00
Original Contract Sum	\$188,229.00

All Contract Sums are exclusive of sale tax.

The Contract Completion Time shall be an additional 20 days, increasing the total contract time to 80 days.



CHANGE ORDER
The Change Order shall not be valid until signed by the Owner and Contractor.

Contractor:	Consultant:	Owner:
Ву:	By:	Ву:
5 8	Terry McDunner	_
		Ken Klein
Craig Alger Presid	Lent Terry McDunner	Executive Director
Printed Name, Title	Printed Name, Title	Printed Name, Title
Date: 11/30/24	Date: <u>12/2/2024</u>	Date:
Accurate Assessment	Atlas Technical Consulting	<b>Snohomish County</b>
Environmental		

## **Accurate Assessment Environmental Change Order Form**

Project Name	New Start Everett Moisture Reme	CO #	2				
Project Address	1602 SE Everett Mall Way, Everett WA 98208						
Project Manager	Craig Alger	Client	Snohomish County				
Requesting Party	Accurate Assessment Environmental (AAE)	Date of Request	11/26/24				

#### **CHANGE REQUEST OVERVIEW**

Description of Changes Needed	A change in the contract price and contract time is needed to allow for the removal of additional mold-impacted GWB and the proper removal/abatement of newly discovered ACM that is applied to the backside of some GWB. In addition to the quantities requested in CO #1, this change order is requesting the scope to be revised to include the removal of 2530 sqft of additional mold impacted GWB, along with the removal of 2600 sqft of ACM impacted GWB that has now been identified. These quantities are estimated to cover the additional work needed to complete the mold remediation, with asbestos abatement compliance, in the remaining 50 units plus auxillary rooms. AAE will work with Atlas to document and quantify additional mold-impacted GWB, ACM impacted or not, as work is carried out in each unit.
Reason for Change	After the initial scope of work began, additional mold impacted GWB has been identified, and ACM was discovered behind the GWB adhered to the backside of GWB in each unit. Change order quantities and locations of both additional mold-impacted GWB and ACM were defined by Atlas.
Support & Justification Documents	See "Former Everett Days Inn - Mold Remediation CO1" spreadsheet (Atlas document) and Photo Documentation for CO1 (AAE document). This Change Order 2 is to cover the remaining quantities in the Atlas document beyond what was requested in the Change Order 1.
Specifications	AAE needs to perform additional work to comply with Class 2 abatement work, including but not limited to Asbestos Abatement Supervisor daily rate, daily air monitoring, proper dust mitigating work procedures, ACM waste transportation and disposal, air monitoring record keeping, and air monitoring laboratory analysis. See WAC 296-62-07712 Requirements for Asbestos Activities in Construction and Shipyard Work.
Additional Information	The Change Order rate for Additional GWB per 10 sqft is \$193.00 before tax. The Change Order rate for added work and regualtory adherence for ACM removal is \$17.15/sqft of ACM material.

#### **CHANGE IN CONTRACT PRICE**

#### **CHANGE IN CONTRACT TIMES**

CHANGE IN	CONTRACT PRICE	CHANGE IN	CONTRACT TIMES
Original Price	\$188,229.00	Original Times	45 days
Net Changes of Previous Change Orders	\$37,540.00	Net Changes of Previous Change Orders in Days	15 Days
Net Increase/Decrease	\$93,419.00	Net Increase/Decrease	20 days
Total Contract Price Pending Approved Changes	\$319,188.00	Total Contract Time with Approved Changes	80 days (Jan 10, 2025)
	_		
Accepted By Signature		Accepted By Signature	
Name & Title	Craig Alger, President	Name & Title	
Date	11/26/24	Date	



Project: Snohomish County - Everett New Start Mold

Date: November 20, 2024

		Qua	Quantity within Scope to be Removed				Additional Qt	y of Material to B	e Removed		Total GWB
Floor	Room	GWB sq ft	GWB with ACM sq ft	RSF with ACM sq ft	Ceiling sq ft	GWB sq ft	GWB with ACM Sq ft	RSF with ACM sq ft	Plywood Subfloor sq ft	Ceiling sq ft	To be Removed b Room
First Floor	110	250	none in initial scope		10	0	0				250
First Floor	111	250	none in initial scope			50	120				300
First Floor	112	300	none in initial scope			0	60				300
First Floor	114	250	none in initial scope			100	0				350
First Floor	115	250	none in initial scope			100	60				350
First Floor	116	250	none in initial scope			100	60				350
First Floor	117	250	none in initial scope			0	60				250
First Floor	118	250	none in initial scope			0	60				250
First Floor	119	250	none in initial scope			0	60				250
First Floor	120	250	none in initial scope			0	60				250
First Floor	121	250	none in initial scope				60				250
First Floor	122	180	none in initial scope				0				180
First Floor	123	150	none in initial scope				60				150
First Floor	124	250	none in initial scope				0				250
First Floor	125	250	none in initial scope				60				250
First Floor	126	250	none in initial scope				60				250
First Floor	127	250	none in initial scope				60				250
First Floor	128	250	none in initial scope				60				250
First Floor	129	250	none in initial scope				60				250
First Floor	130	250	none in initial scope			50	60				300
First Floor	131	700	none in initial scope				340				700
First Floor	132	250	none in initial scope				60				250
First Floor	133	250	none in initial scope				60				250
First Floor	134	250	none in initial scope				60				250
First Floor	135	250	none in initial scope				60				250
First Floor	136	250	none in initial scope				60				250
First Floor	Laundry	250	none in initial scope								250
First Floor	137	180	none in initial scope			70	0		80		250

First Floor         138         100         none in initial scope         100         0           First Floor         139         250         none in initial scope         50         0           First Floor         140         250         none in initial scope         50         0           First Floor         141         250         none in initial scope         0           First Floor         142         250         none in initial notitial         0	200 300 300
First Floor         139         250         none in initial scope         50         0           First Floor         140         250         none in initial scope         50         0           First Floor         141         250         none in initial scope         0           none in initial scope         none in initial scope         0	
First Floor 140 250 none in initial scope 50 0  First Floor 141 250 none in initial scope 0  none in initial scope 0	300
First Floor 141 250 none in initial scope 0	300
none in initial	250
113111001 142 250   Scope	250
Scope First Floor 143 250 none in initial scope 0	250
First Floor 144 250 none in initial scope 0	250
First Floor 145 150 none in initial scope 0	150
Second Floor 201 10 none in initial scope 50 10 50	10
Second Floor 202 50 none in initial scope 50 50	50
Second Floor 203 none in initial scope 50	0
Second Floor 204 50 none in initial scope 50 50	50
Second Floor 205 10 none in initial scope 50 10	10
Second Floor 206 10 none in initial scope 50 10	10
Second Floor 207 none in initial scope 50	0
Second Floor 208 10 none in initial scope 10	10
Second Floor 209 780 none in initial scope 780	780
Second Floor 210 150 none in initial scope	150
Second Floor 211 100 none in initial scope 60	100
Second Floor 212 50 none in initial scope 150 60	200
Second Floor 214 180 none in initial scope 70	250
Second Floor 215 180 none in initial scope 70 60	250
Second Floor 216 20 none in initial scope 80 60	100
Second Floor 217 10 none in initial scope 90 60	100
Second Floor 218 50 none in initial scope 200	250
Second Floor 219 200 none in initial scope 60	200
Second Floor 220 200 none in initial scope 60	200
Second Floor 221 200 none in initial scope 60	200
Second Floor 222 150 none in initial scope	150
Second Floor 223 10 none in initial scope 90 60	100
Second Floor 224 100 none in initial scope 50	150
Second Floor   225   100   none in initial scope   100   60	200

			none in initial									1
Second Floor	226	100	scope			50	60				150	
Canad Flags	007	100	none in initial									
Second Floor	227	180	scope								180	
Second Floor	228	80	none in initial			70	60					
	220		scope			,,,					150	1
Second Floor	229		none in initial			200	60					
			scope								200	1
Second Floor	230		none in initial			250					250	
			scope none in initial								230	1
Second Floor	231	150	scope			50					200	
			none in initial								200	1
Second Floor	232	200	scope				60				200	
Canad Flags	000	000	none in initial				60					1
Second Floor	233	200	scope			50	60				250	
Second Floor	234	200	none in initial			50	60					
	204	200	scope			00					250	1
Second Floor	235	200	none in initial			50	60					
			scope								250	-
Second Floor	236	180	none in initial				60				100	
			scope none in initial								180	1
Second Floor	Laundry	60	scope			90					150	
			none in initial								100	1
Second Floor	237	180	scope								180	
Cocand Floor	220		none in initial			250	C0					
Second Floor	238		scope			250	60				250	]
Second Floor	239	240	none in initial				60					
	200	240	scope								240	1
Second Floor	240	100	none in initial			150	120					
			scope								250	-
Second Floor	241	700	none in initial scope				120	50			700	
			none in initial								700	1
Second Floor	242	700	scope				120	50			700	
0 15	0.40	400	none in initial									1
Second Floor	243	180	scope				60				180	
Second Floor	244	40	none in initial			90	60					
	244		scope			50					130	1
Second Floor	Room	20	none in initial			80						
		45040	scope				1000	450			100	]
		15340				3000	4260	150	80	0	18340	
Original Sco	ne of Work	Sq Ft		Δdditi	onal Scope	- CO 1	Sq Ft					
GWB to be rem		8,760			be remove		670		Г	00.4	470.0	
GWB to be rem		6,330			be removed		2,330				= 470 S	
Total GWB to b		15,090	Total A	DDITIONAL G			3,000	/	<b>'</b>	CO 2:	= 2530	SF
	F with ACM	350		GWB v	vith ACM 1s	st Floor	1,660		L			
				GWB w	ith ACM 2n	d Floor	2,600		Γ	CO 1	= 1660	SF
					RSF wit		150	/ /	$\longrightarrow$			
					Plywood Si	ubfloor	80			UU 2	= 2600	SF
									_			
							05					
				uested CO1 am be removed b		20	Sq Ft 3,000 4,260		Ca	ntracto	r ie not	
				n ACM Requirir		_			1	Contractor is not		
			O V D WILL	RSF with ACM			150				ng the County	
		Plywood Subfloor				80	I for these items					
										1		

Atlas Technical Consulting prepared this chart anticipating one change order. Change Order 01 has been separated from Change Order 02 to allow the contractor to remain working on-site. This prevents the County from incurring additional costs for demobilization, remobilization, and keeps does not place the project to the back of the contractor's work list while the Motion is processed though Council. The approximate two-week time period between our receiving the change request, council approving the motion, the executive signing the change order, and purchasing updating the PO could result in a four-week delay.

# Photo Documentation for Change Order 2

Project Name: Everett New Start Moisture Remediation Prepared by: Accurate Assessment Environmental

Date: 11/30/24

Examples of new mold growth discovered after either baseboard, wallpaper, or GWB within the original protocol was removed. These examples are taken from rooms 218, 216, 217, and 212. Red chalk lines represent Atlas original cut lines. Blue chalk lines represent Atlas new cut lines after the baseboard has been removed.























