SNOHOMISH COUNTY DEPARTMENT OF PUBLIC WORKS	CHANGE ORDER	CHANGE ORDER NUMBER
		10
		7/25/2022
		Page 1 of 1

☒ORDERED BY ENGINEER UNDER SECTION 1-04.4 OF THE STANDARD SPECIFICATIONS. ☐CHANGE PROPOSED BY CONTRACTOR.	**PROJECT IDENTIFICATION** **PROJECT NAME:** Index – Galena Road Floor Repair MP 6.4 – 6.9 **PROJECT NUMBER:** RC1532, RC1774, RR6322, ER-0701(063)
CONTRACTOR ENDORSEMENT: Dennis Diteman Digitally signed by Dennis Diteman DN: C=US, E=dennisd@goodfellowbros.com, O=Goodfellow Bros, OU=Project Manager, CN=Dennis Diteman Date: 2022.08.01 13:25:09-07'00' *SIGNATURE* *DATE* Project Manager *PRINT NAME* *TITLE*	**CONTRACTOR:** Goodfellow Bros, LLC **ADDRESS:** PO Box 598 Wenatchee, WA 98807

All work, materials, and measurements to be in accordance with the provisions of the Standard Specifications and Special Provisions for the type of construction involved.

In consideration of the Standard Specifications Section 1-04.4, make the following revisions to the Contract:

Description

The Contractor shall perform work to repair the uphill roadside slope damaged from a localized landslide that occurred in the vicinity of "I" 46+50 RT to "I" 49+50 RT.

The following new Bid Items and estimated amounts are added to the Contract:

Group 1, RC1532

Item 185, "Slide Repair Excavation and Embankment", in the amount of $105,000 EST.

Item 186, "Rock Backfill for Slide Repair", in the amount of 2,000 TON at the agreed upon unit price of $45.00 per TON.

Materials

Rock backfill for slide repair shall meet the requirements for Quarry Spalls in accordance with Standard Specifications 9-13.1(5).

Construction Requirements

Loose landslide material shall be removed per the direction of the Engineer and embanked on-site from station "I" 36+00 LT to "I" 45+00 LT along the toe of the new road embankment. Embanked landslide material shall be mixed with Topsoil Type B, brush, slash, logs, and other organic vegetation generated from on-site to improve

ORIGINAL CONTRACT AMOUNT	*CURRENT CONTRACT AMOUNT*	*ESTIMATED NET CHANGE THIS ORDER*	*ESTIMATED CONTRACT TOTAL AFTER CHANGE*
$18,105,074.00	**$18,570,780.44**	**$195,000.00**	**$18,765,780.44**

APPROVAL RECOMMENDED Larmore, Brian Digitally signed by Larmore, Brian Date: 2022.08.01 14:04:47 -07'00' *CONSTRUCTION MANAGER* *DATE*	**OTHER APPROVAL RECOMMENDED** *SIGNATURE / REPRESENTING* *DATE*
APPROVAL RECOMMENDED Fahning, Janice Digitally signed by Fahning, Janice Date: 2022.08.01 14:56:23 -07'00' *ENGINEERING SERVICES DIRECTOR* *DATE*	**APPROVED** Douglas W McCormick Digitally signed by Douglas W McCormick Date: 2022.08.01 15:08:47 -07'00' *PUBLIC WORKS DIRECTOR OR COUNTY ENGINEER* *DATE*

$100,000-$200,000

permeability of embankment. After the landslide material has been removed, the excavated area shall be backfilled with free-draining aggregate rock to the lines and grades specified by the Engineer.

Measurement

Slide repair rock backfill will be measured by the ton.

Payment

"Slide Repair Excavation and Embankment" will be paid by force account in accordance with Section 1-09.6 for work associated with excavating, embanking and mixing landslide material with topsoil and other vegetation from on site.

"Rock Backfill for Slide Repair", per ton.

The unit Contract price per ton for "Rock Backfill for Slide Repair" shall be full pay for all costs in furnishing, placing, and compacting the rock backfill.

Contract Time

10 workings days will be added to the Contract Time as a result of this Change Order. Upon completion of the work, additional working days will be evaluated and may be processed in a future change order.

Condition of Award

This change order does not affect the Condition of Award.