



CHANGE ORDER

CHANGE ORDER NUMBER
11
7/29/2022
Page 1 of 2

<input type="checkbox"/> ORDERED BY ENGINEER UNDER SECTION 1-04.4 OF THE STANDARD SPECIFICATIONS. <input type="checkbox"/> CHANGE PROPOSED BY CONTRACTOR.	PROJECT IDENTIFICATION PROJECT NAME: Index – Galena Road Floor Repair MP 6.4 – 6.9 PROJECT NUMBER: RC1532, RC1774, RR6322, ER-0701(063)
CONTRACTOR ENDORSEMENT: <div style="display: flex; justify-content: space-between;"> SIGNATURE DATE </div> <hr/> <div style="display: flex; justify-content: space-between;"> PRINT NAME TITLE </div>	CONTRACTOR: Goodfellow Bros, LLC ADDRESS: PO Box 598 Wenatchee, WA 98807

All work, materials, and measurements to be in accordance with the provisions of the Standard Specifications and Special Provisions for the type of construction involved.

In consideration of the Standard Specifications Section 1-04.4, make the following revisions to the Contract:

Description

The Contractor shall perform work to repair the uphill roadside slope damaged from a localized landslide that occurred in the vicinity of “I” 46+50 RT to “I” 49+50 RT.

The estimated plan quantity of the following Bid Item is increased to continue with the slide repair described in this Change Order:

Group 1, RC1532

Increase Bid Item 185, “Slide Repair Excavation and Embankment” quantity, in the amount of \$237,500 EST., for a revised total plan quantity of \$342,500 EST.

Increase Bid Item 186, “Rock Backfill for Slide Repair”, in the amount of 5,500 TONS at the agreed upon unit price of \$45.00 per TON, for a revised total plan quantity of 7,500 TON.

Materials

Rock backfill for slide repair shall meet the requirements for Quarry Spalls in accordance with Standard Specifications 9-13.1(5).

ORIGINAL CONTRACT AMOUNT	CURRENT CONTRACT AMOUNT	ESTIMATED NET CHANGE THIS ORDER	ESTIMATED CONTRACT TOTAL AFTER CHANGE
\$18,105,074.00	\$18,765,780.44	\$485,000.00	\$19,250,780.44
APPROVAL RECOMMENDED		OTHER APPROVAL RECOMMENDED	
CONSTRUCTION MANAGER DATE		SIGNATURE / REPRESENTING DATE	
APPROVAL RECOMMENDED		APPROVED	
ENGINEERING SERVICES DIRECTOR DATE		SNOHOMISH COUNTY COUNCIL MOTION #: _____	
APPROVAL RECOMMENDED			
PUBLIC WORKS DIRECTOR OR COUNTY ENGINEER DATE		SNOHOMISH COUNTY EXECUTIVE DATE	

CHANGE ORDER

Construction Requirements

Loose landslide material shall be removed per the direction of the Engineer and embanked on-site from station "I" 36+00 LT to "I" 45+00 LT along the toe of the new road embankment. Embanked landslide material shall be mixed with Topsoil Type B, brush, slash, logs, and other vegetation generated from on-site to improve permeability of embankment. After the landslide material has been removed, the excavated area shall be backfilled with free-draining aggregate rock to the lines and grades specified by the Engineer.

Measurement

Slide repair rock backfill will be measured by the ton.

Payment

"Slide Repair Excavation and Embankment" will be paid by force account in accordance with Section 1-09.6 for work associated with excavating, embanking and mixing landslide material with topsoil and other vegetation from on site.

"Rock Backfill for Slide Repair", per ton.

The unit Contract price per ton for "Rock Backfill for Slide Repair" shall be full pay for all costs in furnishing, placing, and compacting the rock backfill.

Contract Time

Upon completion of the work, additional working days will be evaluated and may be processed in a future change order.

Condition of Award

This change order does not affect the Condition of Award