

## **Siemens Industry, Inc.**

**Date:** 11 FEB 2020

**To:** Lolly Huggins – Snohomish County

**RE:** Snohomish County – DJJC DEMO FUTURE HOUSING PODS

Siemens Industry, Inc. (SII) is pleased to provide the following quote for the above referenced project. This quote is based on site survey dated Jan 15, 2020 completed by Paul Pritchard (Siemens), Lolly Huggins (SnoCo), Rob Maez (Nelson Electric). No specifications or addenda(s) have been acknowledged.

---

### **FINANCIAL SUMMARY**

**TOTAL INVESTMENT:               \$ 33,845.00**

---

### **SOLUTION OVERVIEW**

Snohomish County has requested Siemens to assist with the removal of existing cabling related to security devices located in Pod 1S, 1E, 2S, and 2E.

Siemens subcontractor will demo all security device cabling. All de-programming of existing system to be complete by certified Siemens technician.

### **SCOPE OF WORK**

- Provide labor to decommission all field devices from housing units in pod 2 south, 2 east, 1 south and 1 east.
- Each housing unit will need the following items decommissioned, (1) intercom, (1) electric lock, (1) pneumatic lock, (1) red/green status light, (1) red/white status light.
- Each pod will need the duress button and entry and stair intercom's decommissioned.
- All decommissioning of devices will include pulling existing cable back to the nearest J-box and capping wires, pneumatic tubing will be sealed at the device.
- All existing devices to be re-installed without security wiring connected, if replacement or plates required, they are to be provided and installed by others.

### **Alternative #1 SCOPE OF WORK**

- Remove existing cabling for security devices and pull back to the head end equipment room in electrical closet.
- Removal of wiring back to head end to be done on a T&M basis at the technician rate of \$140.00 per hour

**Confidential**

**Snohomish County**

**DJJC Security Device Demo Pod 1S, 1E, 2S, and 2E**

# **Siemens Industry, Inc.**

## **Assumptions/Clarifications**

1. ACAD project drawings: Not Applicable
2. Siemens will furnish material cut sheets for submittal, for Siemens provided materials.
3. Pricing includes project management for the duration of the tentative project schedule.  
Weekly progress meetings are included
4. Work is assumed to be completed during normal business hours Monday – Friday (6am-5pm).
5. Siemens will comply with badging and background check as required by Snohomish County.
6. Price based on free access to work areas with the need for special coordination of work.
7. Prevailing wage project

## **Exclusions**

1. Cable and cable installation.
2. Cutting, painting and patching.
3. Asbestos abatement or containment
4. Fire Alarm system interface, if required.
5. 120VAC by others
6. Network connectivity by others
7. Performance or Payment bonds.
8. Costs associated with schedule acceleration, project meetings, multiple trips onsite due to incompletion of others, or multiple unplanned phases.
9. Low Voltage Electrical permit
10. Washington State Sales Tax.

Please contact me immediately if you have any questions or concerns regarding this proposal. If this proposal is acceptable, please return a signed copy to our office via mail or fax. **This will serve as our notice to proceed with the work described herein.**

### **Proposal accepted by:**

**Name:** Ken Klein

**Company:** Snohomish County

**Title:** Executive Director



4/28/2020

**Signature**

**Date**

### **Proposal submitted by:**

**Paul Pritchard**

**Sales Executive**

**Siemens Industry, Inc.**



2/11/2020

**Signature**

**Date**

**Confidential**

**Snohomish County**

**DJJC Security Device Demo Pod 1S, 1E, 2S, and 2E**